

CLOUD TECH SMART SOLUTIONS

Electrical Installation Documentation

System Documentation & Schematics

Project ID:	STR-001
Location:	Struga
Last Updated:	16 June 2026
Status:	Active / Verified
Maintenance Contract:	Active (Standard SLA)
Last Maintenance:	12 May 2026
Next Maintenance Due:	May 2027

This document is restricted to property owners and authorized personnel only.

SECTION 1: GENERAL SPECIFICATIONS & JOB LOG

1.1 Project Overview & Timeline

This documentation specifies the electrical wiring standards and installation configurations engineered for the STR-001 project in Struga. The system is designed to operate on a 3-phase supply and integrates directly with a smart home management system.

1.2 Safety Compliance

All installation procedures, wire dimensions, and safety layouts comply with IEC 60364 regulations. Residual Current Devices (RCD) are rated at 30mA for shock hazard prevention.

1.3 Job Chronology & Milestones

Job Description	Implementation Dates	Verification
Conduit, Pipes & Underfloor Laying	12 Oct - 05 Nov 2025	Approved / Closed
Cable Pulling & Cabinet Placement	10 Nov - 02 Dec 2025	Approved / Closed
Switchboard Switch Connection & Bus Cabling	15 Jan - 22 Jan 2026	Approved / Closed
Gangs, Switches, Sensors & Video Intercom Setup	10 Feb - 20 Feb 2026	Approved / Closed
System Commissioning, Tests & Final Handover	01 Mar - 15 Mar 2026	Approved / Handed Over

SECTION 1: GENERAL SPECIFICATIONS & JOB LOG

1.4 Cable & Pipe Lengths

Circuit / Material	Cable / Dimension	Quantity Used
Halogen-Free Corrugated Conduit	16 mm (High-density flex)	1,200 meters
Halogen-Free Corrugated Conduit	20 mm (High-density flex)	650 meters
Light Wiring Cabling	NYM-J 3x1.5 mm ² HF	2,400 meters
General Sockets Cabling	NYM-J 3x2.5 mm ² HF	3,100 meters
Switched Sockets / AC Loops	NYM-J 5x2.5 mm ² HF	850 meters
Smart Home Bus Cable	EIB/KNX 2x2x0.8 mm ² Green Shielded	1,200 meters

1.5 Conduit Capacity Guideline

To ensure safety and future-proofing, wire capacities in the corrugated protective tubes are strictly limited:

Tube Dimension	Max Wire Capacity
16 mm Conduit	Max 3x1.5 mm ² wires
20 mm Conduit	Max 3x2.5 mm ² or 5x1.5 mm ² wires
25 mm Conduit	Max 5x2.5 mm ² or Bus lines